

# TOWNSHIP OF MACDONALD, MEREDITH & ABERDEEN ADDITIONAL



IS ACCEPTING TENDERS FOR

## PAVING of Lake Street North, a portion of Bay Street, Municipal Office Parking Lot, & Echo Bay Hall Parking Lot.

- **8035 square meters of HL4 Hot Mix Asphalt – 50mm thickness**
  - Lake Street North – Approximately 4020 square meters, pulverize, raise manholes & valve boxes, add 150mm of A Gravel, Grade, Pave 50mm HL4 (Additional 100 square meters for intersection)
  - Bay Street – Approximately 2680 square meters, pulverize, raise manholes & valve boxes, add 150mm of A Gravel, Grade, Pave 50mm HL4.
  - Municipal Office Parking Lot (208 Church Street)– Approximately 585 Square Meters, pulverize, raise catch basin & valve boxes, add A Gravel as required, Grade, Pave 50mm of HL4.
  - Echo Bay Hall Parking Lot (257 Church Street) – Approximately 650 square meters, pulverize, raise valve box/curb stop, add A Gravel as required, Grade, Pave 50mm of HL4.
- Contractor to provide grade preparation including all materials.
- Please provide proof of General and Liability Insurance
- Please provide a copy of valid and up to date WSIB Clearance Certificate

**Please submit tender marked “Asphalt Tender 2024” to:  
208 Church Street, Echo Bay, ON. P0S 1C0  
Phone: 705-248-2441  
Fax: 705-248-3091  
E-mail: [twpmacd@onlink.net](mailto:twpmacd@onlink.net)**

**Tender closing is Monday March 18, 2024 at 10:30 a.m.  
Tender opening is Monday March 18, 2024 at 10:35 a.m.  
Work to commence as early as: June 1, 2024  
Work to be completed by: August 31, 2024  
Lowest or any tender may not be accepted.**

For more information please contact CAO/Clerk Lacey Kastikainen at 705-248-2441  
If you have any questions, contact Road Superintendent Cody Jarrell at 705-297-6373

## **SPECIAL PROVISION ITEMS**

- ITEM #1      Pulverize existing asphalt:**
- Ensure OPSS 300 is followed, depth of processing to be 150mm.
  - OPSS 330.07.03 will be strictly enforced.
  - Additional granular base may be required as some section of the road simply due to unevenness of existing road.
  - Granular should be placed prior to the full depth reclamation and incorporated into the processed materials.
- ITEM #2      Supply and Place H.L. #4 Asphalt 50 mm Thick**
- Please provide a mix design that has already been approved by other municipalities.
- ITEM #3      AC Adjustment based on MTO Index**
- the payment to the contractor for asphalt pavements will be adjusted based on changes to the MTO asphalt cement price index.

**TOWNSHIP OF MACDONALD, MEREDITH & ABERDEEN ADDITIONAL**

**Paving of Lake Street North & Portion of Bay Street, Office Parking Lot & Echo Bay Hall  
Parking Lot.**

<b>Item No.</b>	<b>Spec. No.</b>	<b>Description</b>	<b>Unit</b>	<b>Quantity</b>	<b>Unit Price</b>	<b>Total Price</b>
1.	330	Pulverize Existing Asphalt	M <sup>2</sup>	8035		
2.	314	Supply, place & compact Granular "A"	M <sup>3</sup>	1200		
3.	310	Supply, place and compact 50mm HL#4 asphalt	M <sup>2</sup>	8035		

**TOTAL TENDER PRICE** \$ \_\_\_\_\_

**HARMONIZED SALES TAX 13%** \$ \_\_\_\_\_

**TOTAL TENDER VALUE** \$ \_\_\_\_\_

**The total Tender value based on the estimated quantities shown in the Form of Tender Prices is hereby repeated in writing;**

---

---

**We agree that the final valuation will be made on the basis of actual quantities as determined by the owner and at the prices as set out in the Form of Tender Prices.**

\_\_\_\_\_  
**Name of Contractor**

\_\_\_\_\_  
**Signing Officer**

\_\_\_\_\_  
**Witness**

\_\_\_\_\_  
**Date**